



Government College of Engineering

Station Road, Osmanpura, Aurangabad – 431 005

Phone : (0240) 2366101, 2366221
E-Mail – principalgeca@yahoo.com

Fax : (0240) 2332835
Web – http://www.geca.ac.in

GECA/MED/QTN/2016-17/ 774 (A)

Date – 1 MAR 2017

To,
Institute web site,
Mechanical Department Notice Board
Institute Notice Board

Subject:- Quotation for Dias for Seminar Hall of Mechanical Department

Dear Sir,

You are requested to send your competitive quotations for following items subject to the following conditions.

CONDITIONS:

- 1 Rates quoted should be FOR AURANGABAD or free delivery at the Institute inclusive of all lead and Lift.
- 2 Detailed specifications of the articles you intend to supply should be given. If not according to the specification, laid down here under.
- 3.The material/work should be supplied/completed within (07) days from the date of order. List of material is given below.
- 4.The earliest deliver period should be quoted if you cannot supply within the period mentioned above.
- 5.Quotation should be in sealed cover and superscripted as "quotations" for Mechanical Department
- Due on : ~~10-03-2017~~, at 4 P.M. 14/03/17
- 6.Quotation should be valid for six months.
- 7.Quotation not complying with the above conditions and incomplete once will not be considered.
- 8.Right to reject any or all quotations rates are with the under signed.
- 9.Rates quoted must be inclusive of All applicable Taxes.

Sr. No.	Description	Quantity
01	Dias for Seminar Hall of Mechanical Department, Supplying and Erecting Dias Length 20 Ft, Width 8 Ft, Height 1 Ft Step size Length 4 Ft. Height 6 Inch (Two Steps are to be provided on each side of the Dias) Using material – Light weight Bricks with cement, sand mortar of standard proportion the dias should be well plastered with 25 mm thickness and 2'*2' vitrified tiles (Ivory color) should be fitted on the dias with front side of the dias and the steps should be fitted with steel gray granite 20mm thickness including full mirror moulding on the front side on the steps and also providing brass patti on the steps front corner, granite should also be provided on the top front 1' X 36' with full moulding	01

Yours faithfully

Principal

Govt. College of Engineering
Aurangabad